

Subdivisional & Meanders, T 5 N R 27 E W M.

Chains	N. bet. Secs. 13 & 14.
	Var.21°15'E.
33.00	Columbia Trail, course E. & W.
37.50	Set post Meander Cor. to Secs. 13 & 14, on bank of Columbia River, about 12 ft. above the water and 3 chs. from it. Made mound and drove charred stake, as per instructions.
	Monday Sept. 16, 1861.
	Var.21°E.
	N. bet. Secs. 34 & 35.
40.00	Set $\frac{1}{4}$ Sec. post; made mound; drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 26, 27, 34 & 35; made mound and drove stake, as per instructions.
	E. on random line bet. Secs. 26 & 35.
	Var.21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.18	Intersect N. & S. line, 17 lks. S. of Sec. Cor. S 89°53'W. on true line bet. Secs. 26 & 35.
40.09	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.18	To Cor. of Secs. 26, 27, 34 & 35.
	N. bet. Secs. 26 & 27.
	Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 22, 23, 26 & 27; made mound and planted charred stake, as per instructions.
	E. on random line bet. Secs. 23 & 26.
	Var.21°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.27	Intersect N. & S. line, 12 lks. S. of Sec. Cor. to 23, 24,