

Exterior Bdy., T 5 N., R. 28 E., W. M.

Chains 80.00	Set post Cor. to Secs. 7, 12, 13 & 18; made mound and deposited charred stake, as per instructions. Surface; nearly flat and rocky.
	N. bet. Secs. 7 & 12. Var. $20^{\circ}15'E$.
31.41	Perpendicular precipice.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
43.41	Set post, Meander Cor. to Secs. 7 & 12, on the bank of Columbia River, 2.00 chs. from the water; made mound as per instructions. Var. $21^{\circ}45'E$.
	Subdivisional Lines, T 5 N R 28 E W M. As surveyed by the same U.S. Dept. Surveyor, Under the same Contract and Date.
	Monday, Sept. 9, 1861. N. bet. Secs. 35 & 36. Var. $20^{\circ}30'E$.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake, as per instructions.
80.00	Set post Cor. to Secs. 25, 26, 35 & 36, in mound with charred stake, as per instructions. Soil; sandy. Surface; undulating, with large sage & greasewood.
	E. on random line bet. Secs. 25 & 36. Var. $20^{\circ}45'E$.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect E. Bdy. of Tp., 28 lks. N. of Cor. to Secs. 25 & 36. N. $89^{\circ}48'W$. on true line bet. Secs. 25 & 36.
40.00	Set $\frac{1}{4}$ Sec. post, in mound with charred stake, as per instructions.
80.00	To Cor. of Secs. 25, 26, 35 & 36.