

Subdivisional Lines, T 5 N R 28 E W M.

Chains	Wednesday, Sept. 11, 1861.
	N. bet. Secs. 34 & 35.
40.00	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
80.00	Set post Cor. to Secs. 26 & 27, 34 & 35; made mound and drove charred stake, as per instructions.
	Over this mile the sage and greasewood are very dense and large, unfavorable for close chaining.
	E. on random line, bet. Secs. 26 & 35.
	Var. 20°30'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post/
80.50	Intersect N. & S. line, 40 lks. N. of Cor. to Secs. 26 & 35. N. 89°43'W. on true line bet. Secs. 26 & 35.
40.25	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
80.50	To Cor. to Secs. 26, 27, 34 & 35.
	N. bet. Secs. 26 & 27.
	Var. 20°30'E.
22.00	Commence to descend.
40.00	Set post $\frac{1}{4}$ Sec. Cor. in mound, with charred stake, as per instructions.
55.00	Foot of rise.
80.00	Set post Cor. to Secs. 22, 23, 26 & 27; made mound and deposited stake, as per instructions.
	Leave sage & greasewood.
	E. on random line bet. Secs. 23 & 26.
	Var. 20°45'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.80	Intersect N. & S. line, 34 lks. N. of Cor. to Secs. 23 & 26. N. 89°44'W. on true line bet. Secs. 23 & 26.
40.40	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.