

Subdivisional Lines, T 5 N R 28 E W M.

Chains	
80.00	Intersect N. & S. line, 5 lks. S. of Cor. to Secs. 14, 15, 22 & 23.
	S.89°58' W. on true line bet. Secs. 15 & 22.
40.00	Set $\frac{1}{4}$ Sec. Cor. post; made mound; drove charred stake, as per instructions.
80.00	To Cor. of Secs. 15, 16, 21 & 22. Land; flat and nearly all sand.
	N. bet. Secs. 15 & 16. Var.20°15'E.
26.00	Columbia Trail, course S.70°E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and deposited charred stake, as per instructions.
64.00	Commence to descend bluff.
80.00	Set post Cor. to Secs. 9, 10, 15 & 16. Made mound; drove charred stake, as per instructions.
	E. on random line bet. Secs. 10 & 15. Var.20°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.12	Intersect N. & S. line at Sec. Cor. W. on true line bet. Secs. 10 & 15.
40.06	Set $\frac{1}{4}$ Sec. post, on top of bluff; made mound; drove charred stake, as per instructions.
80.12	To Cor. to Secs. 9, 10, 15 & 16.
	N. bet. Secs. 9 & 10. Var.21°30'E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions. Surface flat.
55.00	Set Meander Cor. to Secs. 9 & 10, at high water mark, 6.00 chs. from the waters edge; made mound and drove charred stake, as per instructions. Var.21°15'E.