

Subdivisional Lines, T 5 N R 28 E W M.

Chains	<p>island or bar about 40.00 chs. long. Var. 20°30'E. Made mound and drove charred stake, as per instructions.</p>
	<p>W. on true line bet. Secs. 8 & 17. Var. 20°30'E.</p>
40.00	<p>Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.</p>
49.50	<p>Set Meander Cor. to Secs. 8 & 17, at high water mark, on bank of Columbia River, 3 chs. dist. from water; made mound and drove charred stake, as per instructions. Var. 21°E.</p>
	<p>Saturday, Sept. 14, 1861.</p>
	<p>N. bet. Secs. 31 & 32. Var. 21°E.</p>
40.00	<p>Set $\frac{1}{4}$ Sec. post; made mound and deposited stake, as per instructions.</p>
80.00	<p>Set post Cor. to Secs. 29, 30, 31 & 32; made mound and drove charred stake, as per instructions. Surface; undulating. Soil; less sandy, more grass and less sage.</p>
	<p>E. on random bet. Secs. 29 & 32. Var. 21°25'E.</p>
40.00	<p>Set temp. $\frac{1}{4}$ Sec. post.</p>
80.48	<p>Intersect N. & S. line, 15 lks. N. of Cor. to Secs. 28, 29, 32 & 33. N. 89°54'W. on true line bet. Secs. 29 & 32.</p>
40.24	<p>Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions. Top of rise.</p>
80.48	<p>To Cor. of Secs. 29, 30, 31 & 32.</p>