

Subdivisional Lines, T 5 N R 28 E W M.

Chains.

W. on random line bet. Secs. 19 & 30.

Var. 21° 6' E.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

79.90 Intersect W. Bdy. of Tp., 10 lks. S. of Sec. Cor.

S. 89° 46' E. on true line bet. Secs. 19 & 30.

39.90 Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.

67.00 Commence to rise.

70.00 Top of rise.

79.90 To Cor. of Secs. 19, 20, 29 & 30.

W. on random line bet. Secs. 18 & 19.

Var. 21° E.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.89 Intersect W. Bdy. of Tp., 11 lks. S. of post Cor. to Secs. 18 & 19.

S. 89° 56' E. on true line bet. Secs. 18 & 19.

39.89 Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.

70.00 Foot of ridge, course N. & S.

75.00 Top of ridge.

79.89 To Cor. of Secs. 17, 18, 19 & 20.

Soil; sandy with sage, greasewood & bunch grass.

General Description.

Excepting for a few very small patches of soil, within a few rods of the Umatilla and Columbia Rivers, this Tp. is worthless, except for grazing purposes and much less valuable than other portions of Umatilla County, on account of the sand and cactus, which abound.

Meanders of Tp. 5 N., R. 28 E., W. M.
As surveyed by the same U.S. Dept. Surveyor,
Under same Contract and Date.

Wednesday, Sept. 25, 1861.