

Subdivision Sec. 28, T 5 N R 28 E W M.

Chains

- Retracing S.0°09'E. on true line.
- 19.97 Establish 16/10 Cor. and mark same with iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in ground.
- 39.94 Establish 16/13 Cor. and mark same with iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in ground.
- 59.91 Establish 16/16 Cor. and mark same with iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in ground.
- 79.88 South ($\frac{1}{4}$) quarter Sec. Cor., heretofore described.

From the N. ($\frac{1}{4}$) quarter Sec. Cor., heretofore described, I sight to the NW. Cor. of Sec., which is visible and run N.89°58'W.

- 26.08 Intersect easterly right of way of Oregon-Washington R.R. and Navigation Co., and mark same with iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in ground, for witness Cor. to Meander Cor.
- 27.65 Intersect center line of track of O-W RR & N. Co., and mark same with hub at Meander Cor. diam., 24 ins. long, set 24
- 29.22 Intersect westerly right of way line of O-W RR & N. Co. and mark same with iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in ground, for witness Cor. to Meander Cor.
- 40.27 NW. Cor. Sec. 28, heretofore described.

From the 16/10 Cor. of Secs., marked as heretofore described I run to the 16/3 Cor., which is visible, S.89°59'W.

- 22.64 Intersect easterly right of way of O-W RR & N Co., and mark same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.
- 24.16 Intersect center line of track of O-W RR & N Co. and mark same with hub at Meander Cor.
- 25.68 Intersect westerly right of way line of O-W RR & N Co. and marked same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.
- 40.24 16/3 Cor. of Sec. heretofore described.