

Ext. Bdys. Tn. 5 N., R 30 E., W. M.  
 As surveyed by Dolphus S. Payne, U.S. Deputy Surveyor,  
 Under Contract No. 100,  
 Dated Aug. 1, 1861.

## Chains

Sept. 17, 1861.

W. Bdy. of T 5 N., R. 29 E.

Beginning at the S.E. Cor. of T. 5 N., R. 29 E., S.W. Cor. of  
 T 5 N., R. 30 E., on the 1st Standard Parallel N.

Var. 19° 51' E.

N. on W. Bdy. of Secs. 31, T 5 N., R. 30 E.

40.00 Set charred stake, with mound, trench and pits, as per in-  
 structions, for  $\frac{1}{4}$  Sec. Cor.

80.00 Set charred stake, with mound, trench & pits, as per in-  
 structions, for Cor. to Secs. 30 & 31, T 5 N., R 30 E. &  
 Secs. 25 & 36, T 5 N., R. 29 E.

Var. 19° 50' E.

Land; rolling.

Soil; 2nd rate.

N. on line bet. Secs. 30, R. 30 &amp; Sec. 25, R. 29 E.

40.00 Set charred stake, with mound, trench & pits, as per in-  
 structions, for  $\frac{1}{4}$  Sec. Cor.

48.00 Top of hill, descending towards the Columbia River. Height  
 about 600 ft.

64.50 Indian Trail (N. 45° W.)

80.00 Set charred stake, with mound, trench & pits, as per in-  
 structions, for Cor. to Secs. 19 & 30, R. 30 E., and  
 Secs. 24 & 25, R. 29 E.

Var. 19° 30' E.

Soil; sandy, 3rd rate.

N. on line bet. Secs. 19, R. 30 &amp; Sec. 24, R. 29 E.

40.00 Set charred stake, with mound, trench & pits, as per in-  
 structions, for  $\frac{1}{4}$  Sec. Cor.

80.00 Set charred stake, with mound, trench & pits, as per in-  
 structions, for Cor. to Secs. 18 & 19, R. 30 E. & Secs.  
 13 & 24, R. 29 E.

Var. 19° 39' E.

Soil; 2nd rate.