

## Subdivisional Lines, T 5 N R 29 E W M.

Chains	
39.77½	Set ¼ Sec. post; made mound and drove charred stake, as per instructions.
79.55	To Cor. of Secs. 23, 24, 25 & 26.
N. bet. Secs. 23 & 24.	
Var. 21° E.	
40.00	Set ¼ Sec. post; made mound & drove charred stake, as per instructions.
45.00	Commence to descend from table.
80.00	Set post Cor. to Secs. 13, 14, 23 & 24; made mound & drove charred stake, as per instructions.
The last half of this mile is rocky and very poor sand.	
E. on random line bet. Secs. 13 & 24.	
Var. 22° E.	
40.00	Set temp. ¼ Sec. post.
79.55	Intersect E. Bdy. of Tp., 36 lks. S. of Sec. Cor. S. 89° 45' W. on true line bet. Secs. 13 & 24.
39.77½	Set ¼ Sec. post; made mound & drove charred stake, as per instructions.
46.85	Descend perpendicular table.
58.05	Descend perpendicular rock table.
79.55	To Cor. of Secs. 13, 14, 23 & 24.
N. bet. Secs. 13 & 14.	
Var. 22° E.	
40.00	Set ¼ Sec. post; made mound & drove charred stake, as per instructions.
54.00	Walla Walla Trail, course N.E.
70.00	Columbia Trail, course E.
77.00	Descend perpendicular table of rock
80.00	Set post Cor. to Secs. 11, 12, 13 & 14; made mound & drove charred stake, as per instructions.
Surface of this mile is rocky and considerably broken, with dense sage & greasewood.	