

Subdivisional Lines, T 5 N R 29 E W M.

Chains	
	E. on random bet. Secs. 12 & 13.
	Var. 21°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.17	Intersect E. Bdy. of Tp., 16 lks. S. of Sec. Cor.
	S. 89°53'W. on true line bet. Secs. 12 & 13.
38.17	Walla Walla Trail, course N. 80°E.
40.08 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
55.17	Columbia Trail, course N. 85°E.
80.17	To Cor. of Secs. 11, 12, 13, & 14; made mound & drove charred stake, as per instructions.
	N. bet. Secs. 11 & 12.
	Var.
10.13	Set post, Meander Cor. to Secs. 11 & 12, on bank of Columbia River, about 15 ft. above and 2.00 chs. dist. from water, and opposite a low island about 40.00 chs. long, made mound & drove charred stake, as per instructions.
	Var. 20°E.
	N. bet. Secs. 34 & 35.
	Var. 20°30'E.
22.00	Commence ascending.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 26, 27, 34 & 35; made mound & drove charred stake, as per instructions.
	E. on random line bet. Secs. 26 & 35.
	Var. 21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.16	Intersect N. & S. line, 60 lks. N. of Sec. Cor.
	N. 89°34'W. on true line bet. Secs. 26 & 35.
	Commence descending.
40.08	Set $\frac{1}{4}$ Sec. Cor.; made mound & drove charred stake, as per instructions.