

Subdivisional Lines, T 5 N R 29 E W M.

Chains	Var. 21° E.
	E. on true line bet. Secs. 8 & 17.
2.50	Edge of precipice.
40.00	Set $\frac{1}{4}$ Sec. post; made mound of stone.
48.00	Set post, Meander Cor. bet. Secs. 8 & 17; made mound of stone, on bank of Columbia River, 10 ft. above and 2.00 chs. dist. from the water.
	Var. 21° E.
	W. on random bet. Secs. 7 & 18.
	Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.68	Intersect W. Bdy. of Tp., 50 lks. S. of Sec. Cor. to Secs. 7 & 18.
	S. 89° 39' E. on true line bet. Secs. 7 & 18.
40.68	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.68	To Cor. of Secs. 7, 8, 17 & 18.
	Surface flat & rocky.
	Var. 21° E.
	N. bet. Secs. 7 & 8.
1.00	Edge of precipice, 20 ft. high.
11.00	Set post, Meander Cor. to Secs. 7 & 8, on edge of precipice overlooking the Columbia River, about 60 ft. above the water; made mound & drove charred stake, as per instructions.
<p>Meanders, T 5 N R 29 E W M.          As surveyed by the same U.S. Deputy Surveyor,          Under same Contract &amp; date.</p>	
<p>Commencing at the Meander Cor. to Secs. 7 &amp; 12, bet. Rs. 28 &amp; 29 E., Tp. 5 N.</p> <p>Thence up the left bank of the River.</p> <p>S. 68<math>\frac{1}{2}</math>° E., 87.20 chs. to Meander Cor. bet. Secs. 7 &amp; 8.</p> <p>Thence S. 76° E., 49.20 chs. to the Meander Cor. bet. Secs.</p>	