

Subdivision Sec. 32, T 5 N R 29 E W M., Oregon.

Chains

- 40.27 The temp. center $\frac{1}{4}$ Cor. of said Sec. 32, is established as marked by hollow iron post, 2 ins. diam., and 24 ins. long, set 23 ins. in ground.
- Said Sec. 32, being now subdivided in accordance with the Official Circular of March 14th, 1901 (New Circular June 1st 1909), I now proceed with the subdivision of the SW $\frac{1}{4}$ of said Sec.32. From the center $\frac{1}{4}$ Cor., being the NE Cor. of the SW $\frac{1}{4}$ of said Sec.32, marked as heretofore noted, I run on true line N.89°50'W. (The dist. from W $\frac{1}{4}$ Cor. to center $\frac{1}{4}$ Cor. , said Sec.32, having been previously measured in this survey as 40.27 chs.)
- 20.13 Establish 1/16 Cor. on N. line of, and equidistant bet. NW & NE Cors. of SW $\frac{1}{4}$ of said Sec.32, and mark same by an iron post, 1 in. diam., 24 ins. long, set 22 ins. in ground.
- 40.27 Intersect $\frac{1}{4}$ Cor. on W. line, said Sec.32, being NW Cor. of SW $\frac{1}{4}$ of said Sec.32, marked as heretofore noted.
- From the $\frac{1}{4}$ Cor. on W. line, said Sec.32, being the NW Cor. of SW $\frac{1}{4}$ of said Sec.32, marked as heretofore noted, I run on true line S.0°07' E.
- 20.00 Set stake for temp. 1/16 Cor.
- 39.98 Intersect S.C. at SW Cor., said Sec.32, marked as heretofore noted.
- Retracing I run on true line N.0°07'W.
- 19.99 And establish 1/16 Cor. on W. line, and equidistant bet. NW & SW Cors. of SW $\frac{1}{4}$ of said Sec.32, and mark same by iron post, 1 in. diam., 24 ins. long, set 22 ins. in ground.
- From the SW Cor. of said Sec.32, being the SW Cor. of SW $\frac{1}{4}$ of said Sec.32, marked as heretofore noted, I run on true line due E. (the distance from SW Cor. to the $\frac{1}{4}$ Cor. on S. line of said Sec.32) having been previously measured in this survey as 40.28 chs.
- 20.14 Establish 1/16 Cor. on S. line and equidistant bet. SW & SE Cors. of SW $\frac{1}{4}$ of said Sec.32, & mark same by iron post