

Subdivision Sec.32, T 5 N R 29 E W M., Oregon.

Chains

20.14 Establish 1/16 Cor. at center of SW $\frac{1}{4}$ of said Sec.32, at intersection of N & S center line & E & W center line of said $\frac{1}{4}$ Sec., and mark same by iron post, 1 in. diam 24 ins. long, set 22 ins. in ground.

Having subdivided Sec.32, T 5 N R 29 E W M., in accordance with Official Circular of March 14, 1901 (New circular June 1st 1909), and the SW $\frac{1}{4}$ of said Sec.32 in a similar manner, by establishing temp. Cors. at all points necessary for the survey of the land in SW $\frac{1}{4}$ of said Sec.32, I now proceed with the other lines necessary for dividing said $\frac{1}{4}$ Sec. into Farm Units, designated on accompanying plat as Lots 1, 2, 3 & 4.

At the SW Cor. of Secs. 32, T 5 N R 29 E W M., marked by hollow iron post, 3 ins. diam., thence I run N.45°12'E. on line bet. Lots 3 & 4.

28.33 Intersect 1/16 Cor. at center of SW $\frac{1}{4}$, said Sec.32, marked as heretofore described.

Thence I run, N.45°16' E. on line bet. Lots 1 & 2.

28.29 Intersect iron post at NE Cor. of SW $\frac{1}{4}$ of said Sec. 32, marked as heretofore described.

All line necessary for dividing the SW $\frac{1}{4}$ of said Sec. 32, into necessary Farm Units, having been run and the bearing and length of each line given in the foregoing notes, the description, by bearing and distance of each of the irregular subdivisions designated on accompanying plat as Lots 1, 2, 3, & 4, is given below.

Lot 1, beginning at the SW Cor. of the NE $\frac{1}{4}$ of SW $\frac{1}{4}$ of said Sec.32;

Thence S.89°55'E., 20.14 chs. to SE Cor. of NE $\frac{1}{4}$ of SW $\frac{1}{4}$, said Sec.32;

Thence N.0°07'W., 19.93 chs. to NE Cor. of NE $\frac{1}{4}$ of SW $\frac{1}{4}$ of said Sec.32;

Thence S.45°16'W., 28.29 chs. to place of beginning.