

N. Bdy., T 5 N R 30 E W M.

Chains	tions, for $\frac{1}{4}$ Sec. Cor.
42.08	Ascend rocky bluff bank about 20 ft. high, N. & S.
61.50	Descend rocky bluff about 40 ft. high (S.70°W.)
73.00	Descend rocky bluff, about 70 ft. high (S.70°W.), from this point to the river very steep and broken.
77.00	Descend rocky bluff about 30 ft. high.
80.00	Set charred stake, with mound of rocks, trench & pits, as per instructions, for Cor. to Secs. 3 & 4, T 5 N R 30 E., and Secs. 33 & 34, T 6 N R 30 E. Var. 21°E.
W. on true line N. Bdy. Sec. 4, T 5 N R 30 E.	
3.15	Cliff, 50 ft. high.
4.15	Trail, N. 58 $\frac{1}{2}$ ° E.
4.30	River bank, set Meander Cor. post, with rock mound, digging trench or pits being impracticable on account of rock. Var. 19°30'E.
Subdivisional Lines, T 5 N R 30 E W M. As surveyed by Dolphus S. Payne, U.S. Deputy Surveyor, Under Contract No. 100, Dated Aug. 1, 1861.	
Sept. 18, 1861.	
Beginning at the Cor. of Secs. 35 & 36, on S. line of T 5 N., R 30 E. Var. 19°42'E.	
N. on line bet. Secs. 35 & 36.	
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 25, 26, 35 & 36. Var. 19°45'E.
Soil; 2nd rate.	
E. on random bet. Secs. 25 & 36.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. Var.
79.28	Intersect Tr. line, 23 lks. S. of Cor. to Secs. 25 & 36.