

## Subdivisional Lines, T 5 N R 30 E W M.

Chains	
	22 & 23.
	N.89°33'W. on true line bet. Secs. 15 & 22.
40.00	Set charred stake, for $\frac{1}{4}$ Sec. Cor., with mound, trench & pits pits, as per instructions.
80.00	Cor. to Secs. 15, 16, 21 & 22. Soil; 2nd rate.
	N. on line bet. Secs. 15 & 16.
40.00	Set charred stake, with mound, trench & pits, for $\frac{1}{4}$ Sec. Cor., as per instructions.
80.00	Set charred stake, with mound, trench & pits, for Cor. to Secs. 9, 10, 15 & 16, as per instructions. Var.19°51'E. Soil; 2nd rate.
	E. on random bet. Secs. 10 & 15.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.20	Intersect Sec. line, 70 lks. N. of Cor. to Secs. 10, 11, 14 and 15. N.89°30'W. on true line bet. Secs. 10 & 15.
40.10	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.20	Cor. to Secs. 9, 10, 15 & 16. Some rocks. Soil; rather poor.
	N. on line bet. Secs. 9 & 10.
35.00	Begin to descend hill.
40.00	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per in- structions, for Cor. to Secs. 3, 4, 9 & 10. Var.20°45'E. Surface; uneven. Soil; 3rd rate.