

Subdivisional Lines, T 5 N R 30 E W M.

Chains	
13.00	Begin to descend into ravine.
35.000	Bottom of ravine, about 100 ft. deep, S.60°W.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
68.00	Top of hill.
80.20	Cor. to Secs. 27, 28, 33 & 34. Land; hilly. Soil; 3rd rate.
40.00	N. on line bet. Secs. 28 & 29. Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 20, 21, 28 & 29. Var.20°15'E.
40.00	Soil; 2nd rate.
40.00	E. on random bet. Secs. 21 & 28. Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect Sec. line, 53 lks. N. of Cor. to Secs. 21, 22, 27 and 28.
40.00	N.89°38'W. on true line bet. Secs. 21 & 28. Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Cor. to Secs. 20, 21, 28 & 29. Soil; 2nd rate.
40.00	N. on line bet. Secs. 20 & 21. Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 16, 17, 20 & 21. Top of hill descending, towards the Columbia. Var.20°06'E.
	Soil; 2nd rate.