

Subdivisional Lines, T 5 N R 30 E W M.

Chains	E. on random bet. Secs. 16 & 21.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.32	Intersect Sec. line, 30 lks. N. of Cor. to Secs. 15, 16, 21 & 22. N. $89\frac{1}{4}$ 47' W. on true line bet. Secs. 16 & 21.
40.16	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.32	Cor. to Secs. 16, 17, 20 & 21. Land; sandy. Soil; 3rd rate.
Sept. 23.	
	N. on line bet. Secs. 16 & 17.
40.00	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per in- structions, for Cor. to Secs. 8, 9, 16 & 17. Var. $20^{\circ}21'E$. Land; hilly. Soil; 2nd rate.
	E. on random bet. Secs. 9 & 16.
80.58	Intersect Sec. line, 45 lks. N. of Cor. to Secs. 9, 10, 15, and 16. N. $89^{\circ}40'W$. on true line bet. Secs. 9 & 16.
40.29	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.58	Cor. to Secs. 8, 9, 16 & 17. Land; hilly. Soil; 3rd rate.
	N. on line bet. Secs. 8 & 9.
40.00	Set charred stake, with mound, trench & pits, as per in- structions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per in-