

Subdivisional Lines, T 5 N R 30 E W M;

Chains	
79.78	Cor. to Secs. 19, 20, 29 & 30.
	Closing Cor., being in sight, run
	W. on true line bet. Secs. 19 & 30.
5.00	Begin to descend hill towards the Columbia River.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.30	Intersect Tp. line at post Cor. to Secs. 19 & 30.
	Sept. 25.
	N. on line bet. Secs. 19 & 20.
40.00	Set charred stake, with mound, trench, pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 17, 18, 19 & 20.
	Var. 20°21'E.
	Land; sandy.
	Soil; 3rd rate.
	E. on random line bet. Secs. 17 & 20.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.86	Intersect Sec. line, 10 lks. N. of Cor. to Secs. 16, 17, 20 & 21 and 21.
	N. 89°55'W. on true line bet. Secs. 17 & 20.
39.93	Set charred stake, with mound, trench, & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.86	Cor. to Secs. 17, 18, 19 & 20.
	Soil; 2nd rate.
	W. on random bet. Secs. 18 & 19.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect Tp. line, 40 lks. N. of Cor. to Secs. 18 & 19.
	N. 89°42'E. on true line bet. Secs. 18 & 19.