

Subdivisional Lines, T 5 N R 30 E W M.

Chains	<p style="text-align: center;">structions, for $\frac{1}{4}$ Sec. Cor.</p> <p>40.50 Descend steep bluff.</p> <p>42.75 River bottom, E. & W.</p> <p>43.50 Trail, E. & W.</p> <p>44.25 Bank of slough, E. & W. Offset 2.00 chs. E., object on N. shore of slough brs. N. $11\frac{1}{2}^{\circ}$ W., making distance across 9.85 chs. and</p> <p>54.10 Whole distance to N. side of slough about 8.00 chs. E. of this point is a considerable grove of large willow trees above which the slough is dry at the date of survey.</p> <p>80.00 Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 5, 6, 7 & 8.</p> <p style="text-align: right;">Var. $19^{\circ}30'E$.</p> <p>Land on this mile very sandy and barren down to the river bottom, from that N., moist, level & fertile, not subject to inundation.</p>
	<p>Closing Cor. being in sight, run E. on true line bet. Secs. 5 & 8.</p> <p>37.10 N. bank of dry slough, N. 50° E.</p> <p>40.00 Set charred stake, with mound of rocks in dry slough.</p> <p>51.10 S. bank of dry slough.</p> <p>51.60 Trail to Walla Walla, W.</p> <p>Begin to descend hill.</p> <p>80.50 Intersect Sect line at post Cor. to Secs. 4, 5, 8 & 9.</p>
	<p>W. on true line bet. fractional Secs. 6 & 7.</p> <p>40.00 Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.</p> <p>54.50 S. bank of Columbia River.</p> <p>Set charred stake, with mound, trench & pits, as per instructions, for Meander Cor. bet. fractional Secs. 6 & 7.</p> <p style="text-align: right;">Var. $19^{\circ}30'E$.</p>