

Chains

Land; rolling & broken,
 Soil; deep volcanic ash, 2nd rate.
 No timber.
 Undergrowth, sage & greasewood with good growth of bunch
 grass.

W. bet. Secs. 2 & 35.
 Along brink of Juniper Canyon.

40.00 Set basalt stone, 18 x 10 x 10 ins., 12 ins. in the ground
 for $\frac{1}{4}$ Sec. Cor., mkd. $\frac{1}{4}$ on N. face; dig pits, 18 x 18 x
 12 ins., E. & W. of stone, 3 ft. dist, and raised mound
 of earth, $3\frac{1}{2}$ ft. base, $1\frac{1}{2}$ ft. high N. of Cor. No evi-
 dence of old Cor.

43.00 Bottom of ravine, course N.E. and ascend.

52.00 Top of ascent; thence over rolling land.

70.00 Descend rocky bluff, 20 ft. high, brs. N. & S.

80.00 Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for
 Cor. to Secs. 2, 3, 34 & 35, mkd. with 2 notches on E.
 and 4 notches on W. edges; dig pits, 18 x 18 x 12 ins. in
 in each Sec., $5\frac{1}{2}$ ft. dist. and raise mound of earth,
 4 ft. base, 2 ft. high W. of Cor.

All indications of old Cor. have disappeared.

Land; rolling.

Soil; deep, ashy loam, 2nd rate.

No timber.

Undergrowth; sage & greasewood with a good growth of bunch
 grass.

W. bet. Secs. 3 & 34.

Over rolling land.

3.60 A road brs. NW & SE.

6.00 Bottom of ravine, course N.

40.00 Set basalt stone, 14 x 12 x 10 ins., 9 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., mkd. $\frac{1}{4}$ on N. face; deposit 6 large bones