

Resurvey S. Bdy., T 6 N R 30 E W M.

Chains.

mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, E. of Cor.;
pits impracticable.

Land; broken & mountainous.

Soil; rocky, 4th rate.

No timber.

No undergrowth.

Note: The construction of the O.W.R. & N.R.R., has decidedly changed the topography of the river bank at this point, since the original survey of this Bdy. was made by Deputy Payne in 1861, which undoubtedly accounts for the difference in the length of the S. Bdy. of Sec.33.

Field Notes

of the Extension Survey Lines;

and

Meanders of Meredith and Switzler Islands;

also

Small island in Secs.4 & 5,

T 5 N., R 30 E.

of

Willamette Meridian, Oregon

as executed by

Joseph A. Ganong

under

Instructions dated May 19,1913

Group No. 17.

December 6, 1913.

The line bet. Secs. 4 & 5, T 5 N.,R.30 E., if projected N., will cross a small island, therefore, I commence at the Meander Cor. of fractional Secs. 4 & 5, T 5 N R 30 E., which is a charred stake, marked & witnessed as described by the surveyor general.

Thence I run

N., bet. Secs. 4 & 5, counting distance from the Meander Cor. as 30.78 ch. point.