

Exterior Lines, T 5 N R 31 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post, head of small ravine, course W.; drove charred stake; dug pits & raised mound, as per instruct.
80.00	Set post Cor. to Secs. 1, 12, 6 & 7, on top of high hill. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Good grass. Soil; 2nd rate.
N. on E. Bdy. of Sec. 1, T 5 N R 31 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post on top of ridge, sloping W. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Tps. 5 & 6 N Rs. 31 & 32, Secs. 1, 6, 31 and 36, on flat. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass good. Soil; 2nd rate.
May 11th 1865. W. on random bet. Tps. 5 & 6 N., R. 31 E. Var. 21° E.	
At 40 & 80 chs. set $\frac{1}{4}$ & mile posts at 480, not finding Tp. Cor., character of land, being such as to render it difficult to make permanent Cor., I therefore, conclude that the original Tp. Cor. has been removed or destroyed Hence I	
Set Cor. for Tps. 5 & 6 N., Rs. 30 & 31 E., in basin, low sand hills surrounding; drove charred stake; dug pits & raised mound, as per instructions.	
Thence E. on N. Bdy. of Sec. 6, T 5 N R 31 E. Var. 18° 25' E.	
40.00	Set $\frac{1}{4}$ Sec. post, top of steep sand hill; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 5 & 6, 31 & 32, on flat. Drove charred stake; dug pits & raised mound, as per instruct. Land; broken. Grass poor. Soil; 3rd rate.