

Exterior Lines, T 5 N R 31 E W M.

Chains	E. on N. Bdy. of Secs. 1, T 5 N R 31 E. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill, sloping N. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	To post Cor., Tps. 5 & 6, Rs. 31 & 32 E. Land; broken. Some grass. Soil; 2nd rate.
<p>Resurvey of Exterior Lines, T 5 N R 31 E W M. As surveyed by Nicholas O. Walden, U.S. Deputy Surveyor, Under Contract No. 209, Dated July 6, 1874.</p>	
<p>After surveying the subdivisional Lines of the E. tier of Secs. in T 5 N R 31 E. and finding that I could not close within the required limits to all the Cors. on E. Bdy. of Tp. and to the Cor. to Secs. 1 & 2 in N. Bdy., I began at</p>	
<p>The Standard Cor. to Tps. 5 N., Rs. 31 & 32 E. and ran N. on blank line along E. Bdy. of Sec. 36, T 5 N R 31 E.</p>	
40.37	A point, 37 lks. W. of $\frac{1}{4}$ Sec. Cor.
80.00	A point, 115 lks. S. and 45 lks. W. of Cor. to Secs. 25 & 36.
<p>N. on blank line along E. Bdy. of Secs. 25 Var. 21° E.</p>	
41.65	A point, 45 lks. W. of $\frac{1}{4}$ Sec. Cor.
80.00	A point, 215 lks. S. and 78 lks. W. of Cor. to Secs. 24 & 25.
<p>N. on blank line along E. Bdy. of Sec. 24. Var. 20° 30' E.</p>	
42.59	A point, 9 lks. W. of $\frac{1}{4}$ Sec. Cor.
80.00	A point, 311 lks. S. and 13 lks. E. of Cor. to Secs. 13 & 24.
<p>N. on blank line along E. Bdy. of Sec. 13. Var. 22° E.</p>	