

Subdivisional Lines, T 5 N R 31 E W M.

Chains	etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; rolling. Soil; 1st rate, good grass.
	N. bet. Secs. 25 & 26. Var. 21° E.
15.50	Ravine, course W.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for Cor. to Secs. 23, 24, 25 & 26. Drove willow stake, 2 ft. long, 2 ins. sq. in S.E. pit. Land slopes towards ravine. Soil; 1st rate, good grass.
	E. on random line bet. Secs. 24 & 25.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.85	Intersect E. Bdy. of Tp., 53 lks. S. of Cor. S. 89° 37' W. on true line bet. Secs. 24 & 25.
40.42	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.85	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	N. bet. Secs. 23 & 24. Var. 20° 45' E.
38.00	Ravine, course S.W.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 13, 14, 23 & 24. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E.