

Subdivisional Lines, T 5 N R 31 E W M.

Chains	<p>pit.</p> <p>Land; rolling.</p> <p>Soil; 1st rate., good grass.</p>
	<p>E. on random line bet. Secs. 13 & 24.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.08	Intersect E. Bdy. of Tp., 132 lks. S. of Cor. S.89°03'W. on true line
40.04	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.08	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	Oct. 22, 1874.
	Note: Retraced E. Bdy. of Sec. 24 & found it to be 80.96 chs. in length, and the Cor. to Secs. 13 & 24, to be 91 lks. W. of Cor. to Secs. 24 & 25.
	<p>N. bet. Secs. 13 & 14.</p> <p style="text-align: right;">Var. 20°30'E.</p>
40.000	Drove charred stake & raised mound of earth with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound with pits, etc., as per instructions, for Cor. to Secs. 11, 12, 13 & 14. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.
	<p>E. on random line bet. Secs. 12 & 13.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.42	Intersect E. Bdy. of Tp., 184 lks. S. of Cor. S.88°41' W. on true line.
40.21	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.