

Subdivisional Lines, T 5 N R 31 E W M.

Chains

N. bet. Secs. 28 & 29.

Var. 21°E.

40.00 Deposit basalt stone, 4 x 4 x 3, marked with a cross (X) and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.00 Set basalt stone, 12 x 8 x 6, 6 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29.

Land; rolling.

Soil; 1st rate. Good grass.

E. on random line bet. Secs. 21 & 28.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.70 Intersect N. & S. line, 63 lks. N. of Cor.

N. 89°33'W. on true line.

40.35 Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.70 The Cor.

Land; rolling.

Soil; 1st rate. Good grass.

N. bet. Secs. 20 & 21.

Var. 20°30'E.

40.00 Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.00 Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 16, 17, 20 & 21.

Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit.

Land; rolling.

Soil; 1st rate. Good grass.

E. on random line bet. Secs. 16 & 21.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.60 Intersect N. & S. line, 56 lks. N. of Cor.

N. 89°36'W. on true line.