

Subdivisional Lines, T 5 N R 31 E W M.

Chains	E. on random line bet. Secs. 4 & 9.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.22	Intersect N. & S. line, 30 lks. N. of Cor. N.89°47'W. on true line.
40.11	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.22	The Cor. Land; rolling. Soil; 2nd rate. Good grass.
N. on random line bet. Secs. 4 & 5. Var.21°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
75.30	Intersect N. Bdy. of Tp., 595 lks. E. of Cor. S.4°15' E. on true line.
35.30	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
75.30	The Cor. Land; rolling. Soil; 2nd rate. Good grass. Oct.29, 1874.
N. bet. Secs. 31 & 32.	
40.00	Deposit basalt stone, 6 x 5 x 4 (marked with cross); raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Deposit Basalt stone, 6 x 4 x 4, marked with a cross, & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 29, 30, 31 & 32. Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 2nd rate. Good grass.
E. on random line bet. Secs. 29 & 32.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.