

Subdivisional Lines, T 5 N R 31 E W M.

Chains	
	E. on random line bet. Secs. 20 & 29.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.40	Intersect N. & S. line, 219 lks. N. of Cor. N.88°26'W. on true line.
40.20	Deposit basalt stone, 4 x 3 x 3, marked with cross (X); raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.40	The Cor. Land; rolling. Soil; 1st rate. Good grass.
<hr/>	
	W. on random line bet. Secs. 19 & 30.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.38	Intersect W. Bdy. of Tp., 85 lks. S. of Cor. S.89°25' E. on true line.
2.00	Leave Spring Water Canyon, course S.W.
35.00	Enter Spring Water Canyon, course S.W.
40.38	Deposit basalt stone, 3 x 3 x 3, marked with cross (X); raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
45.00	Leave Spring Water Canyon, course N.W.
80.38	The Cor. Land; rolling. Soil; 1st rate. Good grass.
Oct.30th, 1874.	
<hr/>	
	N. bet. Secs. 19 & 20.
	Var.19°30'E.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 17, 18, 19 & 20. Drove fir stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.