

20.

*

Subdivisional Lines, T 5 N R 31 E W M.

Chains	
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; gently rolling. Soil; 2nd rate. Good grass.
W. on random line bet. Secs. 7 & 18.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.88	Intersect W. Bdy. of Tp., 131 lks. S. of Cor. S.89°04' E. on true line.
39.88	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.88	The Cor. Land; gently rolling. Soil; 2nd rate.
N. bet. Secs. 7 & 8. Var. 21°30'E.	
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 5, 6, 7 & 8. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 2nd rate.
E. on random line bet. Secs. 5 & 8.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. & S. line, 231 lks. N. of Cor. N.88°21' W. on true line.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; rolling. Soil; 2nd rate.