

## Subdivisional Lines, T 5 N R 31 E W M.

Chains	<p>W. on random line bet. Secs. 6 &amp; 7.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p> <p>79.35 Intersect W. Bdy. of Tp., 163 lks. S. of Cor. S.88°50' E. on true line.</p> <p>39.35 Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>79.35 The Cor. Land; rolling Soil; 2nd rate. Good grass.</p> <hr/> <p>N. on random line bet. Secs. 5 &amp; 6. Var. 21 ° E.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p> <p>82.00 Intersect N. Bdy. of Tp., 125 lks. W. of Cor. S.0°54' W. on true line.</p> <p>49.00 Leave Juniper Canyon, course S.W.</p> <p>42.00 Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>82.00 The Cor. Land; hilly. Soil; 2nd rate.</p> <p style="text-align: right;">Oct. 31st, 1874.</p> <hr/> <p style="text-align: center;">General Description.</p> <hr/> <p>The land in this Tp. is generally rolling.</p> <p>The soil is of 1st rate quality and adapted to agriculture and grazing purposes.</p> <p>The hills are covered with heavy growth of bunch grass.</p> <p>There are several springs in Spring Water Canyon, in the S. part of the Tp.; which produce abundance of water.</p> <p>Juniper Canyon in the N. has water standing in several places.</p> <hr/>
--------	---