

Exterior Lines, T 5 N R 32 E W M.

Chains	At 40 & 80 chs., set $\frac{1}{4}$ & mile post, 478 chs. 66 lks., Intersect N. & S. line, 2 chs. & 50 lks. S. of post. Hence the correction will be S. $89^{\circ}46'26''$ on true line.
	S. $89^{\circ}46'26''$ E. on N. Bdy. of Sec. 6, T 5 N R 32 E. Var. 21° E.
38.66	Set $\frac{1}{4}$ Sec. post on N. side of Big Hollow on side hill. Drove charred stake; dug pits & raised mound, as per in- structions.
57.00	Dry bed of Branch, some water standing in holes, just below line, course S. of W.
78.66	Set post Cor. Secs. 5, 6, 31 & 32, on N. side of gully. Drove charred stake; dug pits & raised mound, as per in- structions. Land; rolling. Soil; 2nd rate. Grass good.
	S. $89^{\circ}46'26''$ E. on N. Bdy. of Sec. 5, T 5 N R 32 E. Var. 20° E.
20.00	Deep ravine, Spring Water, 15 chs. S. of line.
40.00	Set $\frac{1}{4}$ Sec. post on E. side of ravine; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. to Secs. 4, 5, 32 & 33, on E. side of ravine near bottom. Drove charred stake; dug pits & raised mound as per instructions. Land; broken. Soil; 2nd rate. Grass good.
	S. $89^{\circ}46'26''$ E. on N. Bdy. of Secs. 4, T 5 N R 32 E. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post on E. side of ravine; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. to Secs. 3, 4, 33 & 34, hill side, sloping to W.; drove charred stake; dug pits & raised mound, as