

Subdivisional Lines, T 5 N R 32 E W M.

Chains	
	<p>Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.</p>
	<p>E. on random line bet. Secs. 24 & 25.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.22	Intersect E. Bdy. of Tp., 16 lks. S. of Cor. S.89°53'W. on true line.
40.11	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.22	The Cor. Land; rolling. Soil; 1st rate.
	<p>N. bet. Secs. 23 & 24. Var. 21°30'E.</p>
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 13, 14, 23 & 24. Drove willow stake, 2 ft. long, 2 ins. sq. in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.
	<p>E. on random line bet. Secs. 13 & 24.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.87	Intersect E. Bdy. of Tp., 60 lks. S. of Cor. S.89°34' W. on true line.
39.93	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.87	The Cor. Land; rolling. Soil; 1st rate. Good grass.