

## Subdivisional Lines, T 5 N R 32 E W M.

Chains	S.89°33' W. on true line.
40.35	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.70	The Cor. Land; gently rolling. Soil; 1st rate. Good grass.
N. bet. Secs. 26 & 27.	
Var.20°45'E.	
30.00	Enter flat, brs. N.W. & S.E.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
61.00	Leave flat, brs. N.W. & S.E.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 22, 23, 26 & and 27. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; flat level, upland, gently rolling. Soil; 1st rate.
E. on random line bet. Secs. 23 & 26	
40.00	Setttemp. $\frac{1}{4}$ Sec. Cor.
80.75	Intersect N. & S. line, 60 lks. S. of Cor. S.89° 34' W. on true line.
40.38	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.75	The Cor. Land; rolling. Soil; 1st rate. Good grass.
N. bet. Secs. 22 & 23.	
Var.21°E.	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.