

Subdivisional Lines, T 5 N R 32 E W M.

Chains	etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.60	The Cor. Land; rolling. Soil; 1st rate. Good grass. Nov. 5th, 1874.
	N. bet. Secs. 10 & 11. Var. 21° 15' E.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
57.00	Enter Juniper Canyon, course W.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 2, 3, 10 and 11. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate.
	E. on random line bet. Secs. 2 & 11.
40.00	Set temp. $\frac{1}{4}$ Sec.
80.60	Intersect N. & S. line, 100 lks. S. of Cor. S. 89° 17' W. on true line.
30.00	Enter Juniper Canyon, course S.W.
40.30	Set basalt stone, 16 x 12 x 7, 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
80.60	The Cor. Land; gently rolling. Soil; 1st rate.
	N. on random line bet. Secs. 2 & 3. Var. 21° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
84.98	Intersect N. Bdy. of Tp., 174 lks. E. of Cor. S. 1° 15' E. on true line.