

Subdivisional Lines, T 5 N R 32 E W M.

Chains	<p>Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.</p>
	<p>E. on random line bet. Secs. 28 & 33.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.89	Intersect N. & S. line, 100 lks. N. of Cor. N.89°17' W. on true line.
40.45	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.89	The Cor. Land; gently rolling. Soil; 1st rate.
	<p>N. bet. Secs. 28 & 29. Var.21°30' E.</p>
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs.20,21,28 & 29. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass. Nov. 7th, 1874.
	<p>E. on random line bet. Secs. 21 & 28.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.67	Intersect N. & S. line, 65 lks. N. of Cor. N.89°32' W. on true line.
40.33	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.67	The Cor. Land; rolling. Soil; 1st rate.