

## Subdivisional Lines, T 5 N R 32 E W M.

Chains	N. bet. Secs. 20 & 21.  Var. 21°30'E.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 16, 17, 20 & 21.  Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate.
	E. on random line bet. Secs. 16 & 21.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.84	Intersect N. & S. line, 75 lks. N. of Cor. N. 89°28' W. on true line.
27.50	Bed of ravine, course N.W.
40.42	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec; Cor.
80.84	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	N. bet. Secs. 16 & 17.  Var: 21°30' E.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 8, 9, 16 and 17.  Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.
	E. on random line bet. Secs. 9 & 16.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.