

Subdivisional Lines, T 5 N R 32 W M.

Chains

83.22 Intersect N. Bdy. of Tp., 225 lks. E. of Cor.
S.1°36' E. on true line.

121.00 Bed of Juniper Canyon, course W.

43.22 Drove charred stake and raised mound of earth, with pits,
etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.

83.22 The Cor.

Land; rolling.

Soil; 1st rate. Good grass.

Nov. 9th, 1874.

N. bet. Secs. 31 & 32.

36.50 Spring Water Canyon, course W.

40.00 Drove charred stake and raised mound of earth, with pits,
etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.00 Drove charred stake & raised mound of earth, with pits,
etc., as per instructions, for Cor. to Secs. 29, 30,
31 & 32.

Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.

Land; rolling.

Soil; 1st rate.

E. on random line bet. Secs. 29 & 32.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.94 Intersect N. & S. line at Cor.

W. on true line.

40.47 Drove charred stake and raised mound of earth, with pits,
etc., as per instructions.

80.94 The Cor.

Land; rolling.

Soil; 1st rate.

W. on random line bet. Secs. 30 & 31.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.02 Intersect W. Bdy. of Tp., 187 lks. S. of Cor.