

Subdivisional Lines, T 5 N R 33 E W M.
 As surveyed by same U.S. Deputy Surveyors,
 Under same Contract & date.

Chains.

Commenced the survey of the subdivisional lines of Tp. 5 N.
 R.33 E. of W. M.

May 5th, 1865.

N. bet. Secs. 35 & 36, T 5 N. R.33 E.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 25, 26, 35 & 36.
 Drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling. Grass good.

Soil; 2nd rate.

E. on random line bet. Secs. 25 & 36.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.50 Intersect N. & S/ ^{Tp.} line, at post, from which I run W. on true line.

40.25 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.50 To post Cor.

Land; broken. Grass good.

Soil; 2nd rate.

N. bet. Secs. 25 & 26.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. to Secs. 23, 24, 25 & 26. Drove charred stake dug pits & raised mound, as per instructions.

Land; broken. Grass good.

Soil; 2nd rate.

E. on random line bet. Secs. 24 & 25.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.25 Intersect N. & S. ^{Tp.} line, 30 lks. N. of post, from which