

Subdivisional Lines, T 5 N R 33 E W M.

Chains	I run N.89°37'W. on true line.
40.12	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.25	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
N. bet. Secs. 23 & 24.	
Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound as per instructions.
80.00	Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass good. Soil; 2nd rate.
E. on random bet. Secs. 13 & 24.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.50	Intersect N. & S. Tp. line, 15 lks. N. of post, from which I run N.89°54'W. on true line.
40.25	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.50	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
N. bet. Secs. 13 & 14.	
Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound as per instructions.
80.00	Set post Cor. for Secs. 11, 12, 13 & 14. Drove charred stake