

Subdivisional Lines, T 5 N R 33 E W M.

Chains

dug pits & raised mound, as per instructions.

Land; rolling gently. Grass good.

Soil; 2nd rate.

E. on random line bet. Secs. 12 & 13.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.80 Intersect N. & S. Tp. line, 20 lks. N. of post, from which
I run

N.89°57' W. on true line.

40.40 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised
mound, as per instructions.

80.80 To post Cor.

Land; rolling.

Grass good.

Soil; 2nd rate.

May 6th, 1865.

N. bet. Secs. 11 & 12.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post.

Drove charred stake; dug pits and raised mound, as per
instructions.

80.00 To post Cor. for Secs. 1, 2, 11 & 12.

Drove charred stake; dug pits and raised mound, as per
instructions.

Land; rolling.

Soil; 2nd rate. Good grass.

E. on random bet. Secs. 1 & 12, T 5 N R 33 E

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.25 Intersect N. & S. Tp. line at post, from which I run
W. on true line.

40.12 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised
mound, as per instructions.