

Subdivisional Lines, T 5 N R 33 E W M.

| | |
|--------|--|
| Chains | N. bet. Secs. 15 & 16. |
| | Var. 21° E. |
| 40.00 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised mound, as per instructions. |
| 80.00 | Set post Cor. for Secs. 9, 10, 15 & 16. Drove charred stake; dug pits & raised mound, as per instructions. |
| | Land; rolling. |
| | Grass good. |
| | Soil; 2nd rate. |
| | E. on random bet. Secs. 10 & 15. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post. |
| 80.00 | Intersect N. & S. line, 50 lks. S. of post, from which, I run S. 89° 38' W. on true line. |
| 40.00 | Set $\frac{1}{4}$ Sec. post; dug pits; drove charred stake; raised mound, as per instructions. |
| 80.00 | To post Cor. |
| | Land; rolling. |
| | Grass good. |
| | Soil; 2nd rate. |
| | May 9th, 1865. |
| | N. bet. Secs. 9 & 10. |
| | Var. 21° E. |
| 40.00 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions. |
| 80.00 | Set post Cor. to Secs. 3, 4, 9 & 10. Drove charred stake; dug pits and raised mound, as per instructions. |
| | Land; rolling. |
| | Grass good. |
| | Soil; 2nd rate. |