

Exterior Lines, T 5 N R 34 E W M.
 As surveyed by Wm.H.Odell & Wm.L. Lewis, U.S. Deputy Surveyors,
 Under Contract No. 110,
 Dated Feby. 7th, 1865.

Chains

N. bet. Rs. 34 & 35, on E. Bdy. Sec. 36, T 5 N.

Var. 20° E.

40.00 Set $\frac{1}{4}$ Sec. post.

Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 25, 36, 30 & 31. Land slopes to the E. Drove charred stake; dug pits & raised mound, as per instructions.

This line passes over broken lands. Good grass. Soil; 2nd rate.

N. on E. Bdy. of Secs. 25.

Var. 20° 30' E.

40.00 Set charred post Cor. for $\frac{1}{4}$ Sec.; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 24, 25, 19 & 30. Drove charred stake; dug pits & raised mound, as per instructions.

This line passes over broken land. Good grass.
 Soil; 2nd rate.

N. on E. Bdy. of Secs. 24.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post, on hillside, facing E.

Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 13, 24, 18 & 19.

Drove charred stake; dug pits and raised mound, as per instructions.

Land; broken.

Soil; 2nd rate.

N. on E. Bdy. of Secs. 13.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post, on hill, facing E. Dug pits; drove charred stake & raised mound, as per instructions.