

Exterior Lines, T 5 N R 34 E W M.

Chains

to be 1.47 S. of post.

True line will be S.89°50'E.

S.89°50'E. on true line on N. Bdy. of Sec.6, T 5 N.

Var.21°E.

38.44 Set $\frac{1}{4}$ Sec. post on E. side of ravine, 40 ft. deep. Drove charred stake; dug pits & raised mound, as per instructions.

78.44 Set post Cor. for Secs. 5, 6, 31 & 32. Drove charred stake dug pits and raised mound, as per instructions.

Land; very broken.

Soil; hardly 2nd rate.

S.89°50'E. on true line bet. Secs. 5 & 32.

Var.21°E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 4, 5, 32 & 33; drove charred stake; dug pits and raised mound, as per instructions.

Land; broken. Grass good.

Soil; 2nd rate.

April 14th, 1865:

S.89°50'E. on true line on N. Bdy. of Secs. 4.

Var.21°E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 3, 4, 33 & 34. Drove charred stake; dug pits and raised mound, as per instructions.

This line passes over hilly land. Good grass.

Soil; 2nd rate.

S.89°50' E. on N. Bdy. of Sec. 3.

Var.21° E.