

Exterior Lines, T 5 N R 34 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 2, 3, 34 & 35. Drove charred stake; dug pits and raised mound, as per instructions. Land; hilly. Soil; hardly 2nd rate. Good grass.
S.89°50'E. on true line on N. Bdy. of Secs. 2. Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.
77.00	Pine Creek, 20 lks. wide, course N.W.
80.00	Set post Cor. for Secs. 1, 2, 35 & 36. Drove charred stake; dug pits and raised mound, as per instructions. Land; broken. Soil; hardly 2nd rate. Good grass.
S.89°50'E. on true line on N. Bdy. of Sec.1. Var.21°E.	
15.00	Summit of ridge bet. Pine Creek and Dry Creek. Var.23°E.
40.00	Set $\frac{1}{4}$ Sec. post on hill, facing N. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	To post Cor. of Tp. Land; hilly. Soil; 3rd rate. Good grass.
Subdivisional Lines, T 5 N R 34 E W M. As surveyed by same U.S. Deputy Surveyors, Under same Contract and Date.	
Commenced the survey of Subdivisional Lines of Tp. 5 N., of Base Line of Range 34 East of Willamette Meridian.	
April 10th, 1865.	