

Subdivisional Lines, T 5 N R 34 E W M.

Chains	N. bet. Secs. 11 & 12.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Hillslopes to W. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 1, 2, 11 & 12, land sloping to NW. Drove charred stake; dug pits and raised mound, as per instructions.
	Land; broken and gravelly.
	Soil; hardly 2nd rate.
<hr/>	
	E. on random bet. Secs. 1 & 12.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
62.00	Pine creek, course N.W.
80.65	Intersect N. & S. line, 38 lks. N. of post Cor., from which I run N. 89° 44' W. on true line.
40.32	Set post Cor. for $\frac{1}{4}$ Sec. Drove charred stake; dug pits and raised mound, as per instructions.
80.65	To post Cor. Land; broken. Soil; hardly 2nd rate.
<hr/>	
	N. on random bet. Secs. 1 & 2.
	Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
70.50	Brink of steep bank.
72.50	Foot of bank.
78.00	Pine Creek, 30 lks. wide, course N.W.
79.30	Intersect E. & W. Tp. line, 49 lks. E. of post Cor. for Secs. 1, 2, 35 & 36, from which I run S. 21° E. on true line.
39.30	Set $\frac{1}{4}$ Sec. post Cor. on hillside, sloping to W.; drove charred stake; dug pits and raised mound, as per instructions.
79.30	To post Cor. Land; broken. Soil; 2nd rate.