

Subdivisional Lines, T 5 N R 34 E W M.

Chains

N. bet. Secs. 34 & 35.

Var. 20°E.

40.00 Set  $\frac{1}{4}$  Sec. post Cor. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits and raised mound, as per instructions.

Land; broken.

Grass good.

Soil; good 2nd rate.

E. on random bet. Secs. 26 & 35.

40.00 Set  $\frac{1}{4}$  Sec. post Cor. temp.

79.92 Intersect N. & S. line, 15 lks. S. of post, Cor. for Secs. 25, 26, 35 & 36, from which, I run

S. 89°54'W. on true line.

39.96 Set  $\frac{1}{4}$  Sec. post Cor. on land sloping to W. Drove charred stake; dug pits and raised mound, as per instructions.

79.92 To post Cor.

Land; broken.

Good grass.

Soil; 2nd rate.

N. bet. Secs. 26 & 27.

Var. 21°E.

40.00 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 22, 23, 26 & 27. Land descends gradually to the W. Drove charred stake; dug pits and raised mound, as per instructions.

Land; broken.

Grass good.

Soil; 2nd rate.

E. on random bet. Secs. 23 & 26.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.