

Subdivisional Lines, T 5 N R 34 E W M.

Chains

N. bet. Secs. 28 & 29.

Var. 21° E.

33.50 Trail, course N.W.

40.00 Set  $\frac{1}{4}$  Sec. post, on level. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 20, 21, 28 & 29. Land slopes to the E. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Soil; 2nd rate.

Grass good.

E. on random bet. Secs. 21 & 28.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.

80.16 Intersect N. & S. line, 18 lks. S. of post, from which,  
I run

S. 89° 52' W. on true line.

40.08 Set  $\frac{1}{4}$  Sec. post on land sloping to W.

Drove charred stake; dug pits and raised mound, as per instructions.

80.16 To post Cor.

Land; rolling.

Grass good.

Soil; 2nd rate.

N. bet. Secs. 20 & 21.

Var. 20° E.

40.00 Set  $\frac{1}{4}$  Sec. post Cor. on level. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 16, 17, 20 & 21.

Drove charred stake; dug pits and raised mound, as per instructions.

Land; rolling.

Grass good. Soil; 2nd rate.