

Subdivisional Lines, T 5 N R 34 E W M.

Chains	
	N. bet. Secs. 31 & 32.
	Var.
40.00	Set $\frac{1}{4}$ Sec. post. Land gently sloping to the S.W. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. to Secs. 29, 30, 31 & 32. Land slopes to W. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Good grass. Soil; 2nd rate.
	E. on random bet. Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.15	Intersect N. & S. line, 20 lks. S. of post, from which, I run S.89°41' W. on true line.
40.07	Set $\frac{1}{4}$ Sec. post Cor. Land slopes to S. Drove charred stake, etc.
80.15	To post Cor. Land; broken. Good grass. Soil; 2nd rate.
	W. on random bet. Secs. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.76	Intersect N. & S. line, 20 lks. N. of post, from which, I run N.89°41' E. on true line.
39.76	Set $\frac{1}{4}$ Sec. post on broad dry gulch, course S.W. Drove charred stake; dug pits & raised mound, as per instruct.
79.76	To post Cor. Land; broken. Good grass. Soil; good 2nd rate.