

Subdivisional Lines, T 5 N R 34 E W M.

Chains	N. bet. Secs. 17 & 18. Var. 20° E.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill, sloping to W. Drove charred stake; dug pits & raised mound, as per instructions.
47.51 ⁵⁰	Trail, course N.W.
80.00	Set post Cor. for Secs. 7, 8, 17 & 18. Land slopes to N.E. ✓ Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Good grass. Soil; good 2nd rate.
	E. on random bet. Secs. 8 & 17.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
45.25	Spring branch, 2 lks. wide, course N.W.
79.85	Intersect N. & S. line, 15 lks. S. of post, from which, I run S. 89° 54' W. on true line.
39.92	Set $\frac{1}{4}$ Sec. post, on steep hill side, facing E. Drove charred stake; dug pits & raised mound, as per instructions.
79.85	To post Cor. Good grass. Land; broken. Soil; 2nd rate.
	W. on random bet. Secs. 7 & 18.
11.65	Trail, course N.W.
31.00	Spring branch, 2 lks. wide, course N.W.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.97	Intersect W. Tp. line, 23 lks. N. of post, from which, I run N. 89° 50' E. on true line.
39.97	Set $\frac{1}{4}$ Sec. post, on hill side, facing E. Drove stake; dug pits & raised mound, as per instructions.