

Exterior Lines,
N. Bdy., T 5 N R 35 E W M.

Chains	<p>Mar. 29, 1865.</p> <p>W. on random on N. Bdy. of Sec.4.</p> <p style="text-align: right;">Var.21°E.</p>
25.00	Foot of hill.
30.00	Summit of hill.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
74.35	Road, course N.W.
80.00	Set temp. Sec. Cor. post for Secs. 4, 5, 33 & 32.
	Land; rolling.
	Good grass.
	Soil; 2nd rate.
	<p>W. on N. Bdy. of Sec.5.</p> <p style="text-align: right;">Var.21°E.</p>
31.00	Dry Creek, 20 lks. wide, course N.W.
34.00	" " " " " " S.W.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
44.75	Same creek, course N.W.
80.00	Set temp. post Cor. for Secs. 5, 6, 31 & 32.
	The land on this line is broken.
	Good grass.
	Soil; good 2nd rate.
	<p>W. on random on N. Bdy. of Sec.6.</p> <p style="text-align: right;">Var.21°E.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. post.
78.67	Intersect N. & S. line, 97 lks. S. of post.
	Land; gently rolling.
	Good grass.
	Soil; 2nd rate.
	<p>E. on true line on N. Bdy. of Tp. 5 N., R.35 E., bet. Secs. 31 & 6.</p> <p>Course S.89°43'E. Var.21°E.</p>